

| ITEMS | DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|--------------------------------------|---|----------------|-----|------|--------|
| BESMM 4 - DEMO BOQ | | | | | |
| <u>SUBSTRUCTURE</u> | | | | | |
| <u>Excavating and Filling</u> | | | | | |
| <u>Site Preparation</u> | | | | | |
| A 1.5.1.1 | Preliminary site works, locating underground services, maximum depth not exceeding 100mm thick for water pipes. | Item | | | |
| B 1.5.1.2.2 | Trial pit, to determine ground condition. Maximum depth 300mm at the discretion of the contractor | Nr | | | |
| C 1.5.2.1.1 | Removing trees, girth 50 - 150mm, and backfill materials | Nr | | | |
| D 1.5.4.1.1 | Site clearnace of vegetation and other growth and dispose offsite | m ² | | | |
| E 1.5.5.2.1 | Remove topsoil, average 100mm depth, stored on site | m ² | | | |
| F 1.5.10.1.2 | Retain excavated topsoil on site to temporary spoil heap 50m distance | m ³ | | | |
| EXCAVATION AND FILLING | | | | | |
| G 1.5.6.2.1 | Excavation from strip level, foundation excavation, not exceeding 2m, strip foundation | m ³ | | | |
| H 1.5.9.2.1 | Disposal of excavated materials off site | item | | | |
| CONCRETE | | | | | |
| J 1.11.2.1.2. | Plain in-situ concrete grade 20/25,20mm aggregate, horizontal work, less than 300mm thick in structures | m ³ | | | |
| BLOCK WALL | | | | | |
| K 1.14.1.2.2 | Wall overall thickness 230mm thick battered on both sides in common/ stretcher bond, cement mortar (1:3) | m ² | | | |
| L 1.11.1.1.3 | Plain insitu concrete (1:10), mass concrete in filling voids | m ³ | | | |
| M 1.14.16.1.3 | DPC (Damp Proof Cost) less than 300mm wide, pitch polymer, B.S 743, Bedded in cement mortar (1:3), horizontal | m | | | |
| N 1.11.1.1.1 | Filling obtained from excavated material, less than 500mm deep, 500mm thick, back fill to trench excavation. | m ³ | | | |
| Carried to collection | | | | | |